

Huawei engineering Service: basic package

Sales Package	Service Operations	Main Content	Achieved Goal
Basic	Supervision services power-on and commissioning	1) Inspection before power-on 2) System commissioning 3) System defect elimination 4) Function verification 5) 7*24 hotline support	Complete the normal power-on operation of the system, complete the management system connection, etc., and confirm that the functions are normal



Detailed description of the service package

Before construction (0.1 man-day)

No.	Quotation Item	Responsibility matrix		Baseline man-day
		HW	EPC	
1	Foundation confirmation			0.1
1.1	Construction drawing confirmation	S	R	0.1
1.2	Pouring standard	S	R	
	Levelness requirements	S	R	
	Strength requirements	S	R	
2	Unpacking and Inspection	S	R	0.2
2.1	Material counting	S	R	

Remote installation training for supervision (0.5 man-day)

No.	Quotation Item	Responsibility matrix		Baseline Man-day
		HW	EPC	
3	Installation Guide			0.5
3.1	Installation training	R	S	0.5
	Use training	R	S	
	Power-on training	R	S	
3.2	On-site guidance	R	S	The whole journey
	Hoisting and fixing the cabinet	S	R	
	PCS Installation	S	R	
	DC-DC installation	S	R	
	Installing the SACU	S	R	
	Battery installation	S	R	
Cable connection	S	R		

Onsite commissioning (1 man-day)

No.	Quotation Item	Responsibility matrix		Baseline man-day
		HW	EPC	
4	Deployment commissioning			0.5
4.1	Check Before Power-on	R	S	0.1
4.2	Deployment commissioning	R	S	0.2
4.3	EMS joint commissioning	S	R	0.2
5	Eliminate the defect			
5.1	Eliminate the defect	R	S	
6	Function acceptance			0.5
6.1	Function commissioning	R	S	
6.1.1	Fire fighting system	R	S	
6.1.1.1	Smoke sensory	R	S	
6.1.1.2	Warm sensory	R	S	
6.1.2	Water immersion	R	S	
6.1.3	Door status sensor	R	S	
6.1.4	Illumination	R	S	
6.1.5	Socket	R	S	
6.1.6	Communications	R	S	
6.1.7	Air Conditioning	R	S	